





DRAWN IN SECTION


# EVERY DROP, ACCOUNTED FOR.




# READ IT **TOP TO BOTTOM**

Chapters sit at depths, not page numbers. The gauge on the right edge of every page shows how far down you are, from ground level to the sump.

|      |                        |    |
|------|------------------------|----|
| 0    | GROUND <b>LEVEL</b>    | 01 |
| 500  | THE <b>LOGO</b>        | 05 |
| 1000 | <b>COLOUR</b>          | 10 |
| 1500 | <b>TYPE</b>            | 14 |
| 2000 | <b>VOICE</b>           | 18 |
| 2500 | GRAPHIC <b>DEVICES</b> | 21 |
| 3000 | <b>PHOTOGRAPHY</b>     | 24 |
| 3500 | THE <b>RHINO RANGE</b> | 29 |
| 4000 | ON <b>SCREEN</b>       | 31 |
| 4500 | IN <b>PRINT</b>        | 35 |
| 5000 | MADE <b>THINGS</b>     | 38 |
| 5500 | <b>MOTION</b>          | 41 |
| 6000 | THE <b>FILES</b>       | 42 |
| +350 | THE <b>SUMP</b>        | 43 |




# THE DROP IS ALREADY A SECTION




Cut through any SuDS Enviro product and you get the same picture as the drop: ground on top, water in the middle, foul kept below. Everything the company makes lives under the turf line, and it is specified by depth, diameter and clock position.

So the identity is drawn the way the products are drawn: **in section**. This is our reading of the mark, not its origin story. The mark itself does not change.



# ONE IDEA, **FOUR JOBS**


An idea only earns its place if it can do all four of these at once. The section does.



01 / Device

## A GAUGE AND A CUT

A river staff gauge on every page, and a cut through the ground on every chapter opener. Both are measured, never decorative.



02 / Motion

## SETTLE, THEN RISE

The drop builds the way silt settles: bottom band first, top band last. Then the wordmark rises into place. Nothing spins.



03 / Structure

## CHAPTERS AT DEPTH


The book runs from ground level to the sump. Each chapter sits 500 mm below the last, on the same scale the configurator uses.



04 / A line

## SOMETHING PEOPLE SAY

Every drop, accounted for. Said by an engineer it means the maths works. Said by a site manager it means nothing gets missed.





500 mm

THE LOGO

SuDS Enviro already has a strong family of marks. This chapter sets the rules for using them. It does not redraw them.

| MARK                 | USE IT FOR                                                |
|----------------------|-----------------------------------------------------------|
| Stacked, with slogan | Covers, the website hero, the first page of anything.     |
| Horizontal           | Headers, footers, email signatures, vans, title blocks.   |
| SuDS RHINO lockup    | Anything about the product range rather than the company. |
| The drop             | App icons, avatars, favicons, the seal, small spaces.     |


All four are SuDS Enviro's own artwork, taken from the master files on the live site. Vector masters exist for the horizontal and RHINO lockups; the stacked lockup is held as a PNG only.



The drop, lifted from the horizontal master. Use it where the name is already said.



# HALF A DROP OF CLEAR SPACE



Clear space is half the height of the drop, on every side. In the horizontal lockup the drop is the full height of the logo, so the rule is simply half the logo's height. Nothing else, not even a page edge, comes inside it.

Measure from the master artwork, not from a screenshot with padding.

| MARK                 | PRINT, MIN WIDTH | SCREEN, MIN WIDTH |
|----------------------|------------------|-------------------|
| Horizontal           | 35 mm            | 140 px            |
| Stacked, with slogan | 30 mm            | 120 px            |
| SuDS RHINO lockup    | 30 mm            | 120 px            |
| The drop             | 6 mm tall        | 24 px tall        |
| Clockwork seal       | 20 mm            | 80 px             |

Below the stacked minimum the slogan stops being readable. Switch to the horizontal lockup instead of shrinking further.


500 MM / COLOURWAYS

# SIX WAYS TO SET IT




FULL COLOUR ON PAPER

The default. Use it whenever the ground allows.




FULL COLOUR ON SURFACE

Data sheets, the website, catalogue pages.



REVERSED ON DEEP


Navigation bars, van sides, hoardings.



REVERSED ON INVERT

Foul water material and night-time pieces.

Reversed keeps the drop in full colour and turns the letters white, as the live site does. Black, one colour, is kept for engraving and laser marking only (see Made things).




WHITE ON BLUE

Buttons and banners in the brand blue.



DEEP, ONE COLOUR

One-colour print, stamps, tape.



# IT SETTLES. IT NEVER SPINS.



## WHAT MOVES

- The bands arrive from above and settle bottom first, red then the small green, blue, and the top green last. The way silt settles in a sump.
- The wordmark rises 8 px into place once the drop is complete.
- Ease out on every move. 220 ms between bands.



## WHAT NEVER MOVES

- The drop never rotates, tilts, wobbles or splashes.
- The bands never change order or colour. Red is always at the bottom.
- The letters never animate one by one.

Use the drop alone only where the name is already said  
nearby: app icon, avatar, favicon, the centre of the seal.

500 MM / PLEASE DON'T


# EIGHT THINGS WE HAVE SEEN HAPPEN




Retire the earlier S-and-leaf mark. It still sits in the website asset library.




Retire the earlier thin wordmark, also still in the asset library.



Do not stretch or squash it.



Do not reorder or recolour the bands.




Do not rotate the drop.



Do not set it straight onto a busy photo.



Do not retype the name in Montserrat as a logo.



Do not outline it or add effects.



# 1000 mm

## COLOUR

Keep the four colours SuDS Enviro already uses. Add only what was missing: a reading ground, a dark ground, and a green that can carry text.

1000 mm. The shallowest RHINO inspection chamber we make.

#1D80B9  
RGB 29, 128, 185

**BLUE**  
The bold voice. Headings, buttons, water.  
Live site variable

#005576  
RGB 0, 85, 118


**DEEP**  
Body copy, navigation, the reversed ground.  
Live site variable

#54B54D  
RGB 84, 181, 77


**GREEN**  
The light voice, the land, the outlet node.  
Live site variable

#C34C4A  
RGB 195, 76, 74

**RED**  
Foul water. Used sparingly, always low down.  
In the drop



# FOUR ADDITIONS, EACH WITH A JOB



**SURFACE**

#EEF3F5    RGB 238, 243, 245  
Reading ground and catalogue ground.




**INVERT**

#062A3A    RGB 6, 42, 58  
Dark ground for foul water and night.



**FIELD**


#3D8537    RGB 61, 133, 55  
Green that can carry text on Paper.



**SKY**


#AFDBF4    RGB 175, 219, 244  
Already on the site. Lines and text on dark.

HOW MUCH OF EACH, ACROSS A TYPICAL DOCUMENT



**Autoflo yellow** #FFE313 stays where the live site uses it: the Rhino autoFlo sub-brand, and nowhere else. It is a product accent, not a brand colour.

These are screen values in hex and RGB. Print colours are not specified here: match them to these values on a press proof before any run, and keep the proof as the reference for that printer.




1000 MM / THE AXIS

# CLEAN WATER

Surface water, rainwater and silt. Material for these products sits on Paper or Surface, in Blue and Green.

- RHINO SERSIC inspection chambers
- Catchpits and silt traps (SERS, SERDS)
- SudSceptor hydrodynamic separators
- RhinoPod filters
- RhinoRoFlo and RhinoRoTex flow control
- Rainwater harvesting




This is how the customer meets the products: the site splits every range into foul and surface water solutions, and so does the drop, with red kept at the bottom. The two grounds make the split visible from across a room.


# FOUL WATER

Foul drainage, grease and off-mains treatment. Material for these sits on Invert, with Sky for lines and Red as the one accent.

- RHINO SERFIC inspection chambers
- RhinoLift pumping stations
- Grease traps (RHINO GT)
- Grease separators
- Septic tanks



Products used on both sides, like the chambers and pumping stations, follow the job they are doing in that piece.



1000 MM / CONTRAST, MEASURED

# EVERY PAIRING, WITH ITS RATIO


| TEXT ON              | PAPER         | SURFACE       | SKY           | BLUE          | DEEP          | INVERT        |
|----------------------|---------------|---------------|---------------|---------------|---------------|---------------|
| <b>Ink</b> #0B2B3C   | 14.74<br>AA   | 13.17<br>AA   | 10.01<br>AA   | 3.40<br>LARGE | 1.80<br>FAIL  | <br>FAIL      |
| <b>Deep</b> #005576  | 8.20<br>AA    | 7.33<br>AA    | 5.57<br>AA    | 1.89<br>FAIL  |               | 1.83<br>FAIL  |
| <b>Blue</b> #1D80B9  | 4.34<br>LARGE | 3.88<br>LARGE | 2.95<br>FAIL  |               | 1.89<br>FAIL  | 3.46<br>LARGE |
| <b>Field</b> #3D8537 | 4.56<br>AA    | 4.07<br>LARGE | 3.09<br>LARGE | 1.05<br>FAIL  | 1.80<br>FAIL  | 3.29<br>LARGE |
| <b>Green</b> #54B54D | 2.59<br>FAIL  | 2.32<br>FAIL  | 1.76<br>FAIL  | 1.67<br>FAIL  | 3.16<br>LARGE | 5.78<br>AA    |
| <b>Red</b> #C34C4A   | 4.72<br>AA    | 4.22<br>LARGE | 3.20<br>LARGE | 1.09<br>FAIL  | 1.74<br>FAIL  | 3.18<br>LARGE |
| <b>Sky</b> #AFDBF4   | 1.47<br>FAIL  | 1.32<br>FAIL  |               | 2.95<br>FAIL  | 5.57<br>AA    | 10.19<br>AA   |
| <b>White</b> #FFFFFF |               | 1.12<br>FAIL  | 1.47<br>FAIL  | 4.34<br>LARGE | 8.20<br>AA    | 15.00<br>AA   |

**AA** means 4.5 : 1 or better, fine for body text.  
**Large** means 3 : 1 or better, fine for text at 24 px and up, or 19 px bold. **Fail** means not for text at any size.

The site's light green heading voice measures 2.59 : 1 on white. It fails for text at every size.

So the light voice moves to **Field** on light grounds, 4.56 : 1, the same hue made darker. Green keeps every non-text job: the land, the outlet node, the light voice on Deep and Invert.

Blue reads at 4.34 : 1 on white: headings and buttons yes, body copy no. Body copy is Deep.





# 1500<sub>mm</sub>

## TYPE

Montserrat, the face the live site already uses, in two voices. IBM Plex Mono for anything that is a measurement.

DISPLAY

**MONTSERRAT 800**  
MONTSERRAT 300

Headings, uppercase, two weights in one line.

TEXT

Montserrat 400 and 600 for reading. Sentence case, never centred in long runs.

Body, captions, forms.


Both families are open licence (SIL OFL) from Google Fonts, so any printer, sign maker or web developer can use them without a licence.

Aa  
Aa  
Ø225

MEASUREMENT

IBM Plex Mono 400 / 500  
SERSIC600 · 3000 mm · 9  
o'clock

Codes, sizes, depths, eyebrows.



1500 MM / TWO VOICES

# LIGHT SAYS WHAT IT IS. **BOLD SAYS WHICH ONE.**

## THE **RHINO RANGE**

The live site's own pattern: the generic word light, the name bold.

## INSPECTION **CHAMBERS**

Light for the family, bold for the thing.


## Rhino ***RoFlo***

Sub-brands: Rhino upright, the product name in bold italic, as on the site.

### THE RULES

1. Headings are uppercase, Montserrat 300 then 800 in the same line. Never more than two weights in one heading.
2. The light voice comes first and is the general word. The bold voice is the specific one.
3. On Paper and Surface the light voice is Field and the bold voice is Blue. On Deep and Invert they are Green and White.
4. Body copy is sentence case, Montserrat 400, Deep. Highlight a phrase in Field 600 at most once a paragraph.
5. Every measurement is set in Plex Mono with a space before the unit: 600 mm, Ø225 mm, 5 l/s.
6. Long passages are left aligned. The site's right-aligned blocks stay as feature moments only.

SERSIC600 Ø600 mm  
Inlets 3 / 5 / 6 / 7 / 9 o'clock  
Outlet 12 o'clock Ø225 mm Twinwall  
Depth 1500 mm to soffit Sump 350 mm



# NINE SIZES, SCREEN AND PRINT

| ROLE      | SCREEN PX       | WEIGHT         | PRINT       | SAMPLE                                       |
|-----------|-----------------|----------------|-------------|----------------------------------------------|
| Display   | 72 / 72         | 800 + 300 caps | 60 pt       | THE TWO VOICES                               |
| Heading 1 | 48 / 50         | 800 + 300 caps | 36 pt       | ONE SOLUTION                                 |
| Heading 2 | 32 / 36         | 800 caps       | 22 pt       | FLOW CONTROL                                 |
| Heading 3 | 22 / 28         | 700            | 14 pt       | Choose your inlets                           |
| Lede      | 20 / 29         | 500            | 12 pt       | One-piece HDPE chambers, six diameters.      |
| Body      | 17 / 26         | 400            | 9.5 / 14 pt | Outlet fixed at 12 o'clock on every chamber. |
| Eye brow  | 12 / 16 +0.16em | Mono 500 caps  | 7 pt        | 3000 MM / PHOTOGRAPHY                        |
| Data      | 14 / 20         | Mono 400       | 8 pt        | SEHDS1800 Ø1800 mm                           |
| Caption   | 12 / 17         | Mono 400       | 7 pt        | Re-shot from the 3D file.                    |



Screen sizes are for desktop; on phones, Display and Heading 1 drop to 44 and 34 px. Line lengths stay near 65 characters.

IN USE

## INSPECTION CHAMBERS

One-piece HDPE, benched and channelled. Six diameters from 450 to 1200 mm.

SERSIC600    Ø600 mm  
Inlets 3 / 5 / 6 / 7 / 9  
Outlet 12 o'clock  
Depth to 6000 mm



# SUDS ENVIRO, EVERY TIME

| WRITE                                                                   | NOT                                                      |
|-------------------------------------------------------------------------|----------------------------------------------------------|
| <b>SuDS Enviro</b> in running text                                      | Suds Enviro, SUDS Enviro, SuDS-Enviro, Suds              |
| <b>SuDS Enviro Ltd</b> on legal lines and invoices                      | SuDS Enviro Limited (unless the registered name says so) |
| <b>SuDS</b> for sustainable drainage systems                            | SUDS, Suds, suds                                         |
| <b>the RHINO range</b> for the family                                   | the Rhino Range, the rhino range                         |
| <b>SERSIC600</b> : sales codes in capitals, no spaces, set in Plex Mono | Sersic 600, SERSIC-600                                   |

In all-capital settings, such as the seal and the eyebrows, SUDS ENVIRO is acceptable. Everywhere else the small u stays.


## THE RANGE AS IT IS WRITTEN TODAY, WITH SALES CODES


| PRODUCT                         | CODES             | SIZES          | PRODUCT                     | CODES                  | SIZES              |
|---------------------------------|-------------------|----------------|-----------------------------|------------------------|--------------------|
| <b>RHINO inspection chamber</b> | SERSIC, SERFIC    | 450 to 1200 mm | <b>RhinoLift</b>            | PS50, Mini, Maxi, Aqua | 600 to 1200 mm     |
| <b>Catchpit / silt trap</b>     | SERS, SERDS       | 300 to 1200 mm | <b>RHINO GT</b> grease trap | Jumbo Micro            | under sink, floor  |
| <b>RhinoRoFlo</b> orifice       | SERF300, 450, 600 | 300 to 600 mm  | <b>RhinoPod</b>             | SERP0D1850             | floating cartridge |
| <b>RhinoRoTex</b> vortex        | ROTEX600 to 1200  | 600 to 1200 mm | <b>RhinoDuct</b> drawpit    | SERD                   | 150 mm sections    |
| <b>SudSceptor</b> separator     | SEHDS750 to 3000  | 750 to 3000 mm | <b>RhinoPit</b>             | SERPT600               | 600 mm             |

## FOR SUDS ENVIRO TO DECIDE

Product names are written several ways across the site, the data sheets and the 3D files. We have not picked silently. These need one answer each:

- RHINO or Rhino.** "RHINO SERSIC" on chambers, "Rhino RoFlo" and "RhinoRoFlo" on flow control, "RhinoLift" on pumps. We suggest RHINO for the range and Rhino + name, one word, for named products (RhinoLift, RhinoPod, RhinoRoFlo).
- SudSceptor.** The separator's name breaks the SuDS capitals. Keep it as a product name, or make it SuDSceptor?
- Sales and drawing codes.** The 3D library carries both (SERCIC and SERSIC appear for chambers). One list should map them.
- The three greens.** The logo masters hold #5BB44F, the site holds #54B54D, the RHINO lockup #54B54D. This book uses the site value; the masters should be re-saved to match.





2000 mm

VOICE

SuDS Enviro should sound like the best person on its sales line: someone who knows the product range by heart and gives you the number before you ask.

2000 mm. The deepest adoptable catchpit.

01

SAY THE SIZE.

Ø225 mm outlet at 12 o'clock, not a large outlet. Numbers are what engineers trust.

02

ANSWER FIRST.

The reply to a question goes in the first sentence. The reasons follow.

03

SITE ENGLISH.


Write the way a good contracts manager talks on the phone: plain, specific, calm.

04

ONE JOB PER SENTENCE.

If a sentence needs a second comma, it is usually two sentences.

British English. No exclamation marks. No em dashes. Numbers as figures, with units.



2000 MM / LINE BANK

# LINES THAT CAN BE USED AS THEY ARE

EVERY DROP,  
**ACCOUNTED  
 FOR.**

The working line for the identity.

BESPOKE,  
**STANDARDISED.**

SuDS Enviro's own slogan. Unchanged.

FIVE WAYS IN.  
**ONE WAY OUT.**

The Clockwork chambers: inlets at 3, 5, 6, 7 and 9, outlet at 12.

FROM ROOF  
**TO RIVER.**

Already on the site's Water Journey page.

DOWN TO  
**SIX METRES.**

Non-adoptable chambers go to 6000 mm.

NO MOVING  
 PARTS.  
**NO POWER.**


True of RhinoRoFlo and RhinoRoTex flow control.

THE HOME OF  
**SUDS RHINO.**

From the drawing title block.

BUILT FOR  
 THE BIT  
**NOBODY SEES.**

For recruitment and the about page.



# ON THE PHONE, IN THE INBOX, ON THE SITE

| WHEN                    | WE SAY                                                                                                                  | WE DON'T SAY                                                                     |
|-------------------------|-------------------------------------------------------------------------------------------------------------------------|----------------------------------------------------------------------------------|
| Lead time               | We will confirm a delivery date once we have checked your drawing.                                                      | <del>Super fast turnaround on all orders!</del>                                  |
| A spec question         | A 600 mm chamber takes up to four inlets, at 3, 5, 6, 7 or 9 o'clock. The outlet is at 12.                              | <del>Our revolutionary multi-inlet solution offers unmatched flexibility.</del>  |
| Something we don't make | We don't make that combination. The nearest is a 750 mm chamber with the same inlets.                                   | <del>Unfortunately we are unable to accommodate your request at this time.</del> |
| Adoption                | Adoptable chambers go to 3000 mm to soffit under DCG. Deeper than that, we can talk you through a non-adoptable option. | <del>Fully compliant with all regulations.</del>                                 |
| A problem on site       | Send us a photo and the chamber code from the label. We will call you back.                                             | <del>We apologise for any inconvenience caused.</del>                            |
| Web copy                | Catchpits that hold the silt until you lift it out.                                                                     | <del>Cutting-edge silt management solutions for a sustainable future.</del>      |
| Performance             | Removes over 50% of fine suspended solids, 0 to 200 microns, at design flow.                                            | <del>Industry-leading performance you can trust.</del>                           |


BEFORE, FROM THE LIVE SITE

Improper surface water management can lead to flooding, erosion, and pollution. Effective management involves drainage basins, conveyance systems, and retention basins. At SuDS Enviro, we use advanced techniques to control runoff, reduce erosion, and improve water quality.

AFTER

Rain that can't soak away has to go somewhere. Our chambers, catchpits and flow controls catch it, take the silt and oil out, and let it go at the rate your sewer or river can take. Tell us the site and we will tell you which ones.



2000 mm



2500 mm


GRAPHIC  
DEVICES

Six devices, all harvested from work SuDS Enviro already has: the drop, the configurator, the website and the drawings. Use one or two at a time. They are seasoning.



| DEVICE             | HARVESTED FROM                                                 | USE IT FOR                                       |
|--------------------|----------------------------------------------------------------|--------------------------------------------------|
| The cut            | The site's Site Explorer, where the ground cuts away           | Covers, chapter openers, footers                 |
| The gauge          | River staff gauges; the 500 mm depth steps in the configurator | Progress: page edges, scroll, configurator steps |
| The Clockwork plan | The configurator's clock face and the Clockwork inlet system   | Anything about inlets and outlets                |
| The bands          | The drop's four layers and the site's wave borders             | One divider per spread, the edge of a page       |
| The x-ray          | The ghosted product drawings on the live site                  | Showing what is inside a product                 |
| The ring           | The diameter picker on the site                                | Sizes, in pairs with the plan                    |

# ONE OR TWO AT A TIME




01 THE CUT

Ground on top, strata tinted by depth, a shaft cut to the level that matters. Always measured.



04 THE BANDS

The drop laid flat: green, blue, green, red, in that order, never re-ordered.




02 THE GAUGE

Alternates colour every metre like a river staff gauge. The green marker is where you are.




05 THE X-RAY

A ghosted product drawn in Blue lines, Green on the parts that move water.




03 THE CLOCKWORK PLAN

Outlet green at 12, inlets blue at the positions used. Unused positions stay as faint rings.



06 THE RING

A diameter with its size set along the arc, white on the band. Darker blue for larger sizes.



2500 MM / THE CLOCKWORK SYSTEM


# FIVE WAYS IN. ONE WAY OUT.

Inlets are manufactured at 3, 5, 6, 7 and 9 o'clock, the outlet is fixed at 12. That gives exactly 31 inlet layouts, drawn here. Bespoke for the site, standardised in the factory: the slogan, as a diagram.


**1 INLET**  
5 layouts · 450 mm and up



**2 INLETS**  
10 layouts · 450 mm and up



**3 INLETS**  
10 layouts · 600 mm and up




**4 INLETS**  
5 layouts · 600 mm and up




**5 INLETS**  
1 layout · 750 mm and up



How many inlets a chamber takes depends on its diameter (450 mm: two, 600 mm: four, 750 mm and up: five), from the SERSIC and SERFIC data sheets and the configurator's rule R1.





# 3000 mm

## PHOTOGRAPHY

Two jobs, kept strictly apart. Catalogue images show the product and nothing else, all in one format. Hero images show it in the ground, the yard, the rain.

3000 mm. The deepest adoptable inspection chamber, to pipe soffit, under DCG and SfA7.

### CATALOGUE

Data sheets, the configurator, the product pages, quotes. One fixed format, so forty products read as one set.

### HERO

Covers, the home page, social, hoardings. Shot the way a site photographer would, never in the catalogue format.



3000 mm

3000 MM / CATALOGUE FORMAT

ONE CAMERA,  
EVERY  
PRODUCT

|         |                                              |
|---------|----------------------------------------------|
| Frame   | Square, product centred, filling 78%         |
| Camera  | 22° above level, 35° round from front left   |
| Ground  | Surface #EEF3F5, seamless                    |
| Light   | Key top left, soft fill, soft contact shadow |
| Lens    | Long: 22° field of view, no distortion       |
| Product | As made. Lid on, no props, no pipes          |

This set was rendered from SuDS Enviro's own 3D product files, so it is complete today and every new product can join it the day its file exists. A studio reshoot should copy the same numbers.

Body colour follows the 3D library's defaults until real material samples are matched.



RHINO SERSIC 600



RHINO SERSIC 600, five inlet



RHINO chamber base SEB1050



RhinoPit SERPT600



SudSceptor SEHDS1800



RhinoPod SERPOD1850



RhinoRoFlo POC600



RhinoRoTex C1200



RhinoLift PS50



RhinoLift Mini 2000D




RhinoLift Maxi 1600D




RhinoLift Aqua 190S



RHINO GT Jumbo Micro



RhinoDuct SERD



Rhino FloLock

3000 mm



3000 mm / HERO

# SHOT WHERE **IT LIVES**

Three-quarter or low angles, real light: an overcast morning, low sun, work lights.  
The product exactly as it is made.

3000 MM / HERO SET



Lowering a RHINO SERSIC chamber, housing site, morning



SudSceptor SEHDS1800 arriving on site, low sun



RhinoLift PS50 bedded in, under work lights




Where the water starts: rain on a new street



Where it ends: a clean outfall to the beck

These were re-photographed from the 3D product files with an image model, with the brief to keep each product exactly as it is. They show the direction, not finished photography: check every one against the real product before use, and replace them with the shoot on the next page.



# SHOT LIST, ONE DAY ON SITE, ONE IN THE YARD

| SHOT                               | WHERE AND WHEN                                           | FOR                  |
|------------------------------------|----------------------------------------------------------|----------------------|
| 01 A chamber lowered into a trench | Housing site, overcast morning, low from the trench edge | Hero, covers         |
| 02 Stock yard after rain           | Chambers on pallets, puddles, low sun from the left      | Hero, website        |
| 03 A separator delivered           | Flatbed and crane hook, late afternoon                   | Hero, social         |
| 04 A pumping station at dusk       | Excavation, pea gravel, work lights                      | Foul water material  |
| 05 Rain on a new street            | Kerb-level, gully grate, silver light                    | Openers, the cut     |
| 06 The outfall                     | Headwall into a beck after rain                          | Endings, back covers |
| 07 In the factory                  | Extrusion, thermoforming, a weld being made              | About, recruitment   |
| 08 Details                         | An inlet stub with pipe fitted; a cover flush in paving  | Data sheets, social  |
| 09 The team                        | Real staff in the yard, with their consent               | About, LinkedIn      |
| 10 Studio catalogue                | Every product, to the catalogue numbers                  | Everywhere           |


## THE RULES

- Every image starts from SuDS Enviro's own product, site or people. No stock people.
- Retouch light and dust, never the product. No added inlets, no changed colours.
- Heroes never appear in the catalogue format, and catalogue images never get a background.
- Deliver at least 6000 px on the long side. The site's current photos are too small for hoardings and A1 print.

**Replace first.** The photographs on the live site today are general water scenes. None of them shows a SuDS Enviro product, site or person.




3000 mm



# 3500 mm

## THE RHINO RANGE



SuDS Enviro is the company. RHINO is the range.  
Each product is Rhino plus its own name, with the  
SuDS Enviro drop always somewhere on the page.

Rhino

*RoFlo*

Innovating hydrology. Orifice flow control.

Rhino

*multiFlo*

Versatile system entry. The Clockwork inlets.

Rhino

*autoFlo*


Sensible contingencies. The auto-siphon, in its own yellow.

The three sub-brand lockups and their straplines are from the live site. The rule: Rhino upright in white, the name in bold italic in Green, except autoFlo, which keeps its yellow.

3500 mm

3500 MM / THE RANGE, IN ORDER

# FROM ROOF TO RIVER



The site's Water Journey follows one storm from the roof to the river. The range sits along it in the same order, each product a little deeper than the last because the pipe falls with the ground. This strip is the brochure's contents, the website's product menu and the order of the data sheets.


# 4000 mm

## ON SCREEN


The rebuilt website already speaks most of this language. The book adds three things: the cut, the gauge and real photography.




4000 MM / THE WEBSITE, RUN LOCALLY FROM THE REPO




The RHINO range



A product page



Site Explorer: the cut, already live



Water Journey: roof to river

**01 / Field for the light voice.** Swap the light green heading words to Field on white grounds. Same look, readable at every size.

**02 / The gauge as scroll progress.** A thin staff gauge down the right edge of long pages, green marker at your depth.


**03 / Real photography.** Replace the generic water stock with the shot list. Heroes on the home page, catalogue images on product pages.

4000 MM / ON THE PHONE, WHERE SITE TEAMS ARE


# BUILT FOR A MUDDY THUMB

The configurator was built mobile first, for people on a site or in a van. The phone screens keep the bottom nav bar, big targets and the Clockwork clock face.


The configurator's own navy and greens already sit close to this palette. Moving it onto the same tokens as the website (Deep, Blue, Green, Field) makes them one product.



Home. The stacked lockup and the two-voice line, already live.



Product page. Catalogue image goes here, x-ray on tap.



Configurator, step 0. Moves onto the website tokens.

4000 MM / SOCIAL, 9:16

# ONE FACT PER FRAME

Every post carries one true number: a depth, a clock position, a percentage. The device does the talking, the logo signs off at the bottom.

Text stays inside the middle 70% so platform buttons never cover it. Frames are laid out for portrait, never cropped from landscape.

SuDSenvir

12

9

3

7

6

5

FIVE WAYS IN.  
ONE WAY OUT.

RHINO SERSIC · 3 / 5 / 6 / 7 / 9 · 12

DOWN TO  
SIX METRES.

SuDSenvir

6000 mm

SUDSCEPTOR SEHDS1800

>50%

of fine suspended solids, 0 to 200 microns, removed at design flow.

SuDSenvir

4000 mm

SuDSenvir

EVERY DROP, ACCOUNTED FOR.

LinkedIn cover, 1584 x 396. The left quarter stays clear for the profile avatar (the drop).

4500mm

IN PRINT

Print is where an engineer meets the brand at a desk: the data sheet, the quote, the card left on site.

The data sheet. Deep header with the reversed lockup, the two-voice title, the catalogue image beside the Clockwork plan, then the numbers in Plex Mono. Every figure on it comes from the SERSIC data sheet.

SuDSenviro


DATA SHEET · SERSIC

CHAMBERS / SURFACE WATER

RHINO SERSIC

One-piece HDPE benched and channelled inspection chambers, six diameters from 450 to 1200 mm.





|                      |                                   |
|----------------------|-----------------------------------|
| Material             | HDPE, extruded and thermoformed   |
| Diameters            | 450, 600, 750, 900, 1050, 1200 mm |
| Depth, adoptable     | To 3000 mm to soffit (DCG / SfA7) |
| Depth, non-adoptable | To 6000 mm                        |
| Sump                 | 350 mm integral                   |
| Pipe sizes           | 110 / 160 / 225 / 300 mm          |
| Inlets               | Up to 5, at 3, 5, 6, 7, 9 o'clock |
| Outlet               | Fixed at 12 o'clock               |



BS EN 13598-2 · SfA7 · DCG · Building Regulations Part H1

SuDS Enviro Ltd · 9 Ambleside Court, Chester-le-Street  
DH3 2EB

01224 057 700 ·  
sales@sudsenviron.com

4500 MM / DESK PIECES

# CARDS, QUOTES AND THE INBOX



Cards 85 x 55 mm, uncoated 450 gsm. The back carries the cut. The quote cover uses the same cut at the foot of the page, with fields for the project, never a stock photo. The name and number shown are SuDS Enviro's primary contact and sales line.





# THE RHINO RANGE

Chambers, catchpits, separators, flow control and pumping stations. From roof to river.

PRODUCT GUIDE · EDITION 1

SEPARATE / STORMWATER TREATMENT

## SUDSCEPTOR SEPARATORS

Removes over 50% of fine suspended solids, 0 to 200 microns, at design flows, and up to 99% of coarse solids of 0.1 to 0.4 mm.





SEHDS750 to SEHDS3000  
TSS 0.5 · metals 0.40 · hydrocarbons 0.40



CHAMBER LABEL


### SERSIC600

Ø600 mm · depth \_\_\_\_\_ mm  
Inlets 3 · 6 · 9    Outlet 12  
Made \_\_\_ / \_\_\_ / \_\_\_\_\_  
No. \_\_\_\_\_



Data sheet

A weatherproof label on every chamber, filled in at the factory. Site teams quote the code when they ring, and the QR opens the data sheet. The bands along the foot are the drop laid flat.



5000<sub>mm</sub>

MADE THINGS

Concepts for the things that get made: drawn for OneSign (vehicles, signs, hoardings) and OneLaser (etched and cut pieces).



Van side, long wheelbase panel van, drawn to scale. The cut runs the length of the load area, green turf line at mid-height, darkening to the sills. Concept for OneSign; templates to be taken from the actual vehicle.

5000 MM / ON SITE AND AT THE OFFICE



Heras fence banner, 3400 x 1730 mm, for sites where SuDS Enviro products are going in. Mesh PVC, eyelets every 500 mm. The chamber in the cut stands where the work is. OneSign.



Hi-vis vest, back print. The drop and the name in Deep, one colour, heat transfer. Above the reflective bands only.



RECEPTION WALL

The horizontal lockup in built-up acrylic letters, 10 mm thick, on 25 mm stand-offs, colours matched to Blue, Green and Red by sample. The slogan below in cut vinyl, Deep. About 1500 mm wide for a typical reception wall. Concept for OneSign; sizes to follow a survey.

Rule that applies to all made things: colours are matched to a physical sample before production, and the logo is cut from the vector master, never traced.

5000 mm

5000 MM / ETCHED AND CUT, FOR ONELASER

# PIECES THAT OUTLAST THE PAPERWORK



**The Clockwork seal**, fibre-laser etched into 300 mm brushed stainless. For the reception wall, awards, and the first chamber off a new line. The seal's type is already outlined, so no fonts are needed.




**The service plate**, etched stainless riveted inside the access opening of separators and pumping stations. The code, the pipe sizes and the one maintenance number a service engineer needs.



**The drop, cut** from 6 mm aluminium in four pieces, one per band, mounted 4 mm apart so the layers read in shadow. Powder coated, or left brushed for the factory.

Laser and etched pieces use the one-colour logo files (black and deep). The bands stay in their order even in one colour.



# 5500mm

## MOTION

A 36 second identity film, built as one page and rendered frame by frame. The camera only ever moves down.


| RULE    | VALUE                                   |
|---------|-----------------------------------------|
| Tempo   | 100 bpm, cuts on the beat               |
| Camera  | Down only. Never up, never sideways     |
| Type    | Soft rise 12 px, 600 ms, ease out       |
| Drop    | Bands settle bottom first, 220 ms apart |
| Grain   | Light and even, screen only             |
| Formats | 16:9 and 9:16, laid out again for each  |



01 · Rain on the turf line



02 · The cut opens



03 · Down the shaft, the gauge counts



04 · Five ways in




05 · The bands settle, the wordmark rises



06 · Every drop, accounted for

# EVERYTHING, AT THE BOTTOM OF THE RANGE

Every mark below is in brand-pack/logos as SVG and as a transparent PNG at 2400 px. Type in the seal is converted to outlines, so sign makers and lasers need no fonts.



suds-app-icon-light.svg



suds-app-icon.svg



suds-avatar-deep.svg



suds-avatar.svg




suds-clockwork-seal-filled-deep.s  
vg



suds-clockwork-seal-filled.svg



suds-clockwork-seal-line.svg



suds-drop-black.svg



suds-drop-colour.svg



suds-drop-deep.svg



suds-drop-reversed.svg



suds-drop-white.svg




suds-enviro-horizontal-black.svg




suds-enviro-horizontal-colour.svg



suds-enviro-horizontal-deep.svg



suds-enviro-horizontal-reversed.s  
vg



suds-enviro-horizontal-white.svg



suds-rhino-lockup-black.svg



suds-rhino-lockup-colour.svg



suds-rhino-lockup-deep.svg



suds-rhino-lockup-white.svg

**brand-book.html** and **brand-book.pdf**:  
this book.

**film/**: the identity film, 16:9 and 9:16, 60 fps.

**photography/**: catalogue set and hero set.

**src/**: every script that made this pack, so it  
can be rebuilt.



# EVERY DROP, **ACCOUNTED FOR.**

THE SUMP. 350 MM BELOW THE OUTLET, WHERE THE SILT  
SETTLES AND THIS BOOK ENDS.

